



**KARNATAKA ANTIBIOTICS &  
PHARMACEUTICALS LIMITED**

(A Government of India Enterprise)

ENQUIRY REF. No.	K-E&P/SR/0677/2024-25
DATE	21.06.2024
DUE DATE	01.07.2024 till 1:00 PM

Dear Sir,

Please submit your lowest and competitive offer in a SEALED ENVELOPE, DULY SUPERSCRIBING OUR ABOVE ENQUIRY REF. NO., DATE and DUE DATE on it/ OR MAIL, with other details of F.O.R terms, Taxes, Credit period, Delivery offered, Name of the Make, Detailed Specification etc., for the below Supply or Service

SI No	Item Code	Item Description	Uom	Qty
01	----	DPP1 STERILE AREA AHU REPAIR WORK AS PER BOQ ENCLOSED AS ANNEXURE	NO.	01

Please ensure that your offer reaches us on or before Due Date by courier OR Speed post to below office address:

*M/s. Karnataka Antibiotics and Pharmaceuticals Limited  
Plot No.37, Arka The Business Centre  
NTTF Main Road, Peenya Industrial Area  
2<sup>nd</sup> Phase, Bengaluru-560058  
Ph. No.080-23571590*


OR you can also mail us to our email: [puren@kaplindia.com](mailto:puren@kaplindia.com)

NOTE:

01. PLEASE VISIT OUR SITE FOR BETTER UNDERSTANDING THE SCOPE OF WORK AND **HAVE AN MOM COPY WITH E&P TEAM AND ATTACHED WITH QUOTATION IS MANDATORY.**
02. IF YOU ARE NOT PARTICIPATING IN THE TENDER PLEASE SEND A REGRET LETTER.
03. VENDOR HAS TO QUOTE AS PER OUR TENDER BOQ ONLY IN YOUR COMPANY LETTER HEAD.

Thanking you,

Yours faithfully,  
For KARNATAKA ANTIBIOTICS  
& PHARMACEUTICALS LIMITED

  
YUVARAJA. M  
DY. MANAGER – PURCHASE DEPT.  
MOB: 9945317873

## BOQ for AHU repair work

- a. AHU double-skinned construction panels (pre coated GI Sheet & inner skin being of plain GI Sheet) are damaged needs to rectify by fixing new panels with proper support. The unit panel is double skin of GSS powder coated sheet metal, cabinet type, modular construction and skin thickness should be not less than 0.8 mm for outer skin and 0.8 mm for inner skin. All panels shall be sealed (anti fungicide sealant material) against the framework, with required doors. Cable entry gland needs to be provided on the AHU casing.
- b. Pre filter frame needs to be provide with standard filter size (combination filters)
- c. AHU connected dampers needs to be change (dampers shall be low leakage type leaves, Coloured graduation & Tamper proof locking arrangement) *make: Matrix Metal/ System Air / Trose.*
  - i. Fresh air damper
  - ii. Supply air damper
  - iii. Return air damper
- d. Cooling coil changing, cooling coil capacity and dimensions must match to existing coil. Piping connection must include (cooling coil connection and drain line).
- e. Drain Tray needs to change for new
- f. Removing and mounting back of existing blower & motor.
- g. Canvas needs to be provide for blower.
- h. Providing heaters bank frame (2 heaters bank)

Sl. No.	AHU No.	Area	Make	Model	Air Qty (CFM)	Drive	Motor				
							HP/KW	Pole	RPM	Make	Phase
1	AHU-1	Filling, Preparation & Blending	ETA		10,000	Belt	10/7.5	4	1440	ABB	3

Note:

1. Vendor must visit the site else will be disqualified.
2. After site visit if any deviation found must quote with separate addendum.
3. During execution vendor must use PPE, safety requirements.
4. Supply, installation and commissioning is under vendor scope.
5. Complete Units must be mounted on a continuous common base frame & with suitably rated serrated rubber pads shall be considered.

*Nob*  
20/06/2024  
E(HVNK)

*DM*  
DM(MKM)

*SRD*  
21/06/2024  
SM(SRD)