



**KARNATAKA ANTIBIOTICS &  
PHARMACEUTICALS LIMITED**

(A Government of India Enterprise)

ENQUIRY REF. No.	K-E&P/DP/SR/0819/2024-25
DATE	05.07.2024
DUE DATE	11.07.2024 till 1:00 PM

Dear Sir,

Please submit your lowest and competitive offer in a SEALED ENVELOPE, DULY SUPERSCRIBING OUR ABOVE ENQUIRY REF. NO., DATE and DUE DATE on it/ OR MAIL, with other details of F.O.R terms, Taxes, Credit period, Delivery offered, Name of the Make, Detailed Specification etc., for the below Supply or Service

Sl No	Item Code	Item Description	Uom	Qty
01	MGW2551	CIVIL WORK FOR TRAY DRIER INSTALLATION AS PER TECHNICAL BID/BOQ ENCLOSED AS ANNEXURE	NO.	01

**SERVICE REQUIRED AT OUR AYUSH PLANT, DHARWAD**

Please ensure that your offer reaches us on or before Due Date by courier OR Speed post to below office address:

*M/s. Karnataka Antibiotics and Pharmaceuticals Limited  
Plot No.37, Arka The Business Centre  
NTTF Main Road, Peenya Industrial Area  
2<sup>nd</sup> Phase, Bengaluru-560058  
Ph. No.080-23571590*

OR you can also mail us to our email: [puren@kaplindia.com](mailto:puren@kaplindia.com)

NOTE:

01. PLEASE VISIT OUR SITE FOR BETTER UNDERSTANDING THE SCOPE OF WORK
02. IF YOU ARE NOT PARTICIPATING IN THE TENDER PLEASE SEND A REGRET LETTER.
03. VENDOR HAS TO QUOTE AS PER OUR TENDER BOQ ONLY IN YOUR COMPANY LETTER HEAD.

Thanking you,

Yours faithfully,  
For KARNATAKA ANTIBIOTICS  
& PHARMACEUTICALS LIMITED

YUVARAJA. M  
DY. MANAGER – PURCHASE DEPT.  
MOB: 9945317873

**KARNATAKA ANTIBIOTICS AND PHARMACEUTICALS  
LIMITED,**

**AYUSH PLANT- DHARWAD**

PR No. 2025D00009

Date: 18.06.2024

**Technical Bid**

**Sub: CIVIL WORK FOR TRAY DRIER INSTALLATION (MGW2551)**

**Location:** TABLET GRANULATION

**Note:** Before quoting, please need to be visit the site and refer area and any other requirements for execution of work.

SL NO	DESCRIPTION	QTY
1.	Breaking o fexisting Civil wall and shifting from premises (Size- 3'W x 8'H x 6" Thickness- 2 no's)	50SFT
2.	Construction of Civil wall and ½" plastering on both side. (Size- 3'W x 8'H x 6" Thickness - 2 no's) by red bricks Cement- Ultratech/ACC	50SFT
3.	Interior wall painting Re-constructed wall Painting with 2 coat putty to be done and 1 coat primer, 2 coat satin emulsion Day break 0942 painting Asian	150SFT
4.	Shifting the old Tray drier from Granulation to store front area Size of the Tray drier-2300mm Width x 2800mm Height	1 no
5.	Shifting and positioning of new Tray drier from day store area to granulation area Size of the Tray drier-2300mm Width 2800mm Height	1 no
6.	Epoxy Re coating on existing floor 1 mm thickness Surface preparation to be done for smooth finish, damage epoxy area to be rectified. Apply 1mm thick epoxy top coat Epoxy Colour - Existing (EP light grey - RAL 7035) or approved by KAPL color	110 SMT
7.	Re coating of epoxy coving on existing coving 1 mm thickness Surface preparation to be done for smooth finish, damage epoxy coving area to be rectified. Apply 1mm thick epoxy top coat coving Size: 4"LX 4"H Epoxy Colour - Existing (EP light grey - RAL 7035) or approved by KAPL color	90 RMT






Terms and conditions:-

1. The Contractor shall inspect and examine the Site and its surroundings and shall satisfy himself before submitting his tender as to the nature of the Site, the quantities and nature of work and material necessary for the completion of the Works.
2. The scope of the supply will be complete in the all respect and any material, component or accessories not specifically stated in this specification but necessary for trouble free operation shall be deemed to be included.
3. The vendor shall supply material and should carry out installation / fixing.
4. Vendor shall carry all the tools required for work
5. Loading, unloading and storage of material at site.
6. Vendor should have past well experience in execution of work
7. Left out items at site to be cleared after completion of work
8. Transportation and any other charges to be included
9. The project is complete only after successful Installation, testing and Verification
10. GST as applicable at the time of billing.
11. Water and Electricity will be provided by KAPL.
12. The billing should be charged on actual only.
13. Epoxy and false ceiling should not be damage.

Company name .....

Name: .....

Seal and Signature: .....

Prepared by	Checked by		Reviewed by	Approved by
				
JE(SBP)	AM(BSL)	SM(NG)	AGM(RK)	GM (SK)