



**KARNATAKA ANTIBIOTICS &
PHARMACEUTICALS LIMITED**

(A Government of India Enterprise)

ENQUIRY REF. No.	K-E&P/SR/1506/2024-25
DATE	14.10.2024
DUE DATE	22.10.2024 till 1:00 Pm

Dear Sir,

Please submit your lowest and competitive offer in a SEALED ENVELOPE, DULY SUPERSCRIBING OUR ABOVE ENQUIRY REF. NO., DATE and DUE DATE on it. Mentioned other details of F.O.R terms, Taxes, Credit period, Delivery offered, Name of the Make, Detailed Specification etc., for the below Supply or Service

Sl No	Item Code	Item Description	Uom	Qty
01	---	PU FLOORING, EPOXY FLOORING & COVING WORK BOQ ENCLOSED AS ANNEXURE	NO.	01

Please ensure that your offer reaches us on or before Due Date by courier OR Speed post or by Hand in sealed cover only to below office address:

M/s. Karnataka Antibiotics and Pharmaceuticals Limited
Plot No.37, Arka The Business Centre,NTTF Main Road, Peenya Industrial Area
2nd Phase, Bengaluru-560058 Ph. No.080-23571590

NOTE:

01. PLEASE VISIT OUR SITE FOR BETTER UNDERSTANDING THE SCOPE OF WORK
02. IF YOU ARE NOT PARTICIPATING IN THE TENDER PLEASE SEND A REGRET LETTER.
03. VENDOR HAS TO QUOTE AS PER OUR TENDER BOQ IN YOUR COMPANY LETTER HEAD.
04. QUOTATION MUST BE SUBMITTED IN TWO SEALED COVERS (TECHNICAL & COMMERCIAL/PRICE BID) SEPARATELY AND TO BE PLACE IN ONE ENVELOP OR ELSE YOUR PROPOSAL WILL NOT BE CONSIDERED.

IF YOU NEED ANY CLARIFICATION, PLEASE CONTACT US.

Thanking you,

Yours faithfully,
For KARNATAKA ANTIBIOTICS
& PHARMACEUTICALS LIMITED



YUVARAJA. M
DY. MANAGER – PURCHASE DEPT.
MOB: 9945317873

KARNATAKA ANTIBIOTICS AND PHARMACEUTICALS LTD.


PROJECT: DPP1 UPGRADATION WORK (UZBEKISTAN PRE-AUDIT OBSERVATION)

SL. No.	DESCRIPTION	UNIT	QTY	RATE	AMOUNT	REMARKS
FINISHED GOODS QUARANTANE AREA						
P.1	4mm PU Floor Providing and laying 4mm thick PU flooring including screed, thoroughly scarifying the existing surface with electric scarifier, creating anchor joints on feather edges. Laying scratch (prime) coat and allowed to set, followed by laying PU floor as per approved shade to get monolithic jointless finish etc., complete as per specifications.	SQM	260			
P.2	PU Coving The existing covings shall be levelled with resin topping fine sanded and finished with two coats of Polyurethane Paint/Highsolid PU Coating. Existing cement coving shall be removed and debries shift from factory primises	SQM	180			
P.3	2mm Epoxy Floor Preparing the surfce and eliminating the total dust so as to obtain a sound surface. Creating anchor cuts on the feather ends and applying Epoxy primer and allowing it to set. Laying 2mm thick self leveling Epoxy floor.	SQM	220			
TOTAL AMOUNT						
GST @18 %						
GRAND TOTAL AMOUNT						

Note:

- 1) Before quoting, Vendor must visit the site to understand the scope of the work else will be disqualified (Mandotry: MOM copy needs to attach)
- 2) Vendor should include all supply & labour charges, hidden charges will not entertained.
- 3) Safety requirement must follow during the execution of the work and also must meet statutory requirements like ESI/Insurance etc.,
- 4) Billing must made as per actual measurement
- 5) Technical data sheet must attach, as per site condition if any missing work/quantity needs to quote with separate addendum
- 6) Technical data sheet must attach during submission of quote.
- 7) After completion of work remaining material needs to take back.


JE(SHR)


E(HVNK)


DM(MKM)


SM(SRD)


DGM(KDP)