



ENQUIRY REF. No.	K-E&P/SR/0000/2024-25
DATE	15/10/2024
DUE DATE	23/10/2024 till 1:00 PM

Dear Sir,

Please submit your lowest and competitive offer in a SEALED ENVELOPE, DULY SUPERSCRIBING OUR ABOVE ENQUIRY REF. NO., DATE and DUE DATE on it. Mentioned other details of F.O.R terms, Taxes, Credit period, Delivery offered, Name of the Make, Detailed Specification etc., for the below Supply or Service

SI No	Item Description	Uom	Qty
01	FRP HCL TANK AND CIVIL WORK AT DM WATER PLANT	NOS	01

Please ensure that your offer reaches us on or before Due Date by courier OR Speed post or by Hand in sealed cover only to below office address:

**M/s. Karnataka Antibiotics and Pharmaceuticals Limited
Plot No.37, Arka The Business Centre,NTTF Main Road, Peenya Industrial Area
2nd Phase, Bengaluru-560058 Ph. No.080-23571590**

TECHNICAL CLARIFICATION

BOQ ATTACHED

NOTE:

NOTE:

1. PLEASE VISIT OUR SITE FOR BETTER UNDERSTANDING THE SCOPE OF WORK.
2. IF YOU ARE NOT PARTICIPATING IN THE TENDER PLEASE SEND A REGRET LETTER.
3. VENDOR HAS TO QUOTE AS PER BOQ ONLY IN YOUR COMPANY LETTER HEAD.

IF YOU NEED ANY CLARIFICATION,PLEASE CONTACT US.

Thanking you,

Yours faithfully,
For KARNATAKA ANTIBIOTICS
& PHARMACEUTICALS LIMITED

**RAMESHA B
ASST. GEN. MANAGER - MATERIALS
MOB: 9945317873**

KARNATAKA ANTIBIOTICS AND PHARMACEUTICALS LTD, PEENYA

BOQ for FRP & Civil work at DM water plant acid tank

Sl No	Description	Unit	Quantity	Rate	Amount
1	Earth work excavation in foundation trenches in all soils including hard soil but excluding hard rock, upto a depth not exceeding 1.5m etc., complete as per specifications and as per directions of Engineer-in-charge.	Cum	6.00		
2	Providing & laying plain cement concrete 1:4:8 including shuttering (1 cement: 4 coarse sand: 8 graded stone aggregate 40mm nominal size) using coarse aggregate of 40mm down size for leveling course in foundations and other similar works at all level & depth etc., complete as per specifications and as per directions of Engineer-in-charge.	Cum	7.00		
3	Providing & laying in position reinforced cement concrete of M25 grade using stone aggregate of 20mm down size for footings, machine foundation, raft including necessary shuttering etc., complete as per specifications and as per directions of Engineer-in-charge. (consider steps for HCL tank cleaning pupouse)	Cum	10.00		
4	Providing Thermo-Mechanically Treated bars of grade Fe-500D or more Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position, binding and anchoring to adjacent members wherever necessary complete as per Design including cost of material, labour, usage charges complete as per specifications. Dia of steel 10 mm (The laps and wastages shall not be measured separately)	Kg	850.00		
5	Construction of Brick/Block Masonry in CM 1:6, the rate should including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge. (Stairecase block masonry work to be consider for HCL tank clenaing pupouse) 150 mm solid block.	Sqm	60.00		
6	Providing 15 mm cement plaster of mix 1:4 (1 cement: 4 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	140.00		
9	Supply and fixing of 3 mm thick FRP corrugated sheet including L angles for cladding support of existing width & the same with SS u bolts (HCL acid) at desired intervals as directed by the engineer in charge. Rate to include all tools, tackles, lifts, scaffolding etc., complete as per specifications & as per directions of Engineer-in-charge.	Sqm	50.00		
	<u>Note: Avoid lapping on length wise</u>				
10	Existing wall concrete portion, chamber to be scrubbed for removing the dust portion, providing & fixing Fiber Reinforced Polymer (FRP) lining paint covering to concrete bed, chambers including all tools, tackles, scaffolding etc., complete as per specifications & as per directions of Engineer-in-charge.	Sqm	100.00		
	A) 7 Chambers of dimenssion (2 feet * 2 feet * 2 feet)				
	B) Acid tank wall portion				
11	Construction of block/brick masonry chamber work of size 2'0" x 2'0" including excavation, pcc, masonry, plastering, precast RCC chamber cover of heavy duty, cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Nos	2.00		
12	Supply of 2'0" x 2'0" precast RCC chamber cover of heavy duty including frame etc., complete as per specifications and as per directions of Engineer-in-charge.	Nos	2.00		
13	Providing and laying UPVC pipe for 6" plumbing pipe line connection to Chamber including PCC laying in joints, earth work in soil, back filling and finishing as per engineer incharge .	Rmt	20.00		
TOTAL AMOUNT					
GST %					
GRAND TOTAL AMOUNT					

Note:-

- 1) Before quoting, Contractor must visit the site to understand the scope of the work & MOM copy attached with quotation.
- 2) Contractor should include all supply & labour charges
- 3) Safety norms to be taken care by Contractor only
- 4) Actual measurement to be taken at site
- 5) Debris to be shift from factory premises.
- 6) ESIc statutory to be vendor scope

JE (SHR)

DM(SKS)

SM(SRD)

27/08/24

P.T.O
Attachee
Vendor Rat